



Lanka IOC

LANKA IOC PLC
LEVEL 20, WEST TOWER, WORLD TRADE CENTRE,
ECHELON SQUARE,
COLOMBO - 01
SRI LANKA

- 1 TENDER NUMBER : LIOC/ ENG/ PT/ 03/ 2017-18
- 2 NAME OF WORK : PROVISION OF FALL ARRESTOR SYSTEM IN TLF GENTRIES AND CALIBRATION TOWER AT LIOC TERMINAL TRINCOMALEE.
- 3 COMPLETION TIME: 08 WEEKS
- 4 PLACE OF WORK: LIOC TERMINAL TRINCOMALEE
- 5 BID BOND: LKR 38,370.00
- 6 DUE DATE & TIME : 16/06/2017 @ 1030 Hrs

SCHEDULE OF WORKS					
SN	ITEM DISCRIPTION	QTY	RATE	UNIT	AMOUNT
	SECTION I:DISMANTLING OF MS PIPES BETWEEN TANKS, CIVIL WORKS FOR PIPELINE PEDESTALS, MS STRUCTURAL WORKS ETC AND PIPELINE WORKS				
1	Horizontal Anchorage Lifeline System on Cable Line - This particular permanent anchorage to a user who has to constantly move along a horizontal track. It comprises of a stainless steel wire rope grade 316 of 8 mm diameter running all along the horizontal track. It is installed at the ends using special Universal Extremity plates. The intermediate brackets hold the wire in position all along the length of the wire and are installed at intervals of 10m to 15 mtrs. The line is maintained in tension with the help of Tensioner at one end, while the other end has a swage less termination on to the Universal Extremity plate. Life line length is 11m. The system is confirms to EN - 795 Type C.	12	130000.00	EA	1,560,000.00
2	Carriage Body - The Stainless Steel Carriage Shuttle connects the user to the line with the help of a retractable block, and moves smoothly without interruption along the entire length of the horizontal line and also through the intermediate brackets, ensuring 100% anchorage of the user at all times.	12	37000.00	EA	444,000.00
3	Retractable Block polymer casing with GI Wire and Carabiner - Casing made up of high impact strength Polymer, to prevent breakage and is nearly indestructible wire rope of dia 4.5 mm minimum breaking strength is 12 kN. Conforms to EN 360:2002.	12	48500.00	EA	582,000.00
4	Rhino Harnesses - Attachment Elements - One chest attachment D - Ring and a Dorsal attachment D ring for all Arrest. Two Lateral attachment D ring for work positioning compliance EN 358: 1999	12	20,000.00	EA	240,000.00
5	Structural modification and fixing chargers	12	42,500.00	EA	510,000.00
	GRAND TOTAL				3,336,000.00
	QUOTE RATE IN TERMS OF PERCENTAGE OVER ESTIMATED AMOUNT GIVEN ABOVE				
1	PLUS (+) IN FIGURES				
	PLUS (+) IN WORDS				
2	MINUS (-) IN FIGURES				
	MINUS (-) IN WORDS				
3	AT PAR				

NOTE

- 1 The amount quoted towards the tender shall be arrived at based on applying the percentage quoted on the above indicated estimated amount.
- 2 In case "0" percentage is quoted then it shall be presumed that the tenderer shall accept to carry out the works at par.
- 3 VAT at prevailing rate shall be paid on the above quoted amount.